

**Adam Weishar, C.E.T.**  
Director of Public Works  
Municipality of Kincardine  
Email: aweishar@kincardine.ca



**All correspondence to be addressed to:**  
Municipality of Kincardine - Public Works  
1475 Concession 5, RR5  
Kincardine, ON N2Z 2X6  
Phone 519-396-3468 ext 7119  
Fax: 519-396-1430

## **PUBLIC NOTICE**

### **HURON TERRACE FORCEMAIN REPLACEMENT PRINCES STREET – BRUCE AVENUE TO KINCARDINE AVENUE FORCEMAIN INSTALLATION, SIDEWALK INSTALLATION, ROAD PAVING, AND MISCELLANEOUS WATER SERVICE REPLACEMENT**

**PROJECT NO. 17318A**

#### **Introduction**

The Municipality of Kincardine is proceeding with a municipal infrastructure project to replace an existing sanitary forcemain that extends from the Huron Terrace Sewage Pumping Station (SPS) to the Kincardine Wastewater Treatment Plant on Bruce Avenue. As part of the project, affected road sections will be reconstructed and the culvert spanning the Stewart Drain on Bruce Avenue, will be replaced. The project is being completed in phases, with the section along Bruce Avenue being undertaken now and the section of Princes Street commencing the week of September 8<sup>th</sup>, 2020.

#### **Project Details**

Starting on September 10<sup>th</sup>, the asphalt on Princes Street between Bruce Avenue and Kincardine Avenue will be removed followed by the work items summarized below:

- Installation of a new 450mm diameter sanitary sewage forcemain under the west lane of Princes Street.
- The removal and replacement of the curb and gutter along the west side of Princes Street from Bruce Ave. to Mun. No. 244 Princes Street.
- The installation of a new concrete sidewalk within the west boulevard from Bruce Ave. to the termination point with the existing sidewalk near Kincardine Ave. and the school property.
- The cutting, removal, and replacement of a portion of the driveways intersected by the sidewalk along the west side of the roadway including Mun. No.'s 192, 198, 204, 214, 224, 234, 238, and 244.
- The replacement of the water services to Mun. No.'s 198, 204, 214, 224, 234, 238, and 244.
- Some disturbance and repair to the driveways on the east side of the road will be necessary as part of the water service replacement at Mun. No.'s 199 and 203.
- Full asphalt restoration within the curb lines of the roadway.

The final paving of the road should be complete by late October.

The project is being administered by engineering staff from B. M. Ross and Associates Limited, Project Engineers retained by the Municipality of Kincardine to design the proposed infrastructure replacement project. The infrastructure and road construction is being completed by Birnam Excavating Ltd who has been selected through the tendering process.

**Additional Details of the Infrastructure Installation are as follows:**

## **Project Information**

### **B. M. Ross and Associates Limited**

Contract Administrator: Dale Erb, P.Eng. 519-524-2641  
Construction Observation: Peter Doy 519-524-2641

### **Birnam Excavating**

Project Manager Derek Baines 519-828-3449

### **Boulevards**

- Disturbed grass boulevards will be reconstructed with topsoil and sod.
- Prior to construction, property owners along the west side of the road are advised to remove any planting beds (i.e., flowers, shrubs and hedges), any underground sprinkler systems, any heated driveway systems, and any fencing from within the road allowance and relocate onto their private property.
- Note, excavation for the water service installations may encroach onto private property as required to provide appropriate transitions. These areas will be restored as outlined in these notes.

### **Sidewalk Location**

- The new sidewalk will be located on the west side of the road immediately adjacent to the curb line.

### **Driveway Restoration**

- Where driveways need to be cut to account for the new sidewalk, driveway materials on the house side of the sidewalk will be matched to the existing where possible.

### **Waste Collection during Construction**

- Garbage and Recycling bins should be put out at the roadside, as usual. The Contractor will ensure that the garbage and recycling are collected. It is requested that residents write their address on the outside of the bins to ensure they are returned to the correct address.

### **Utilities**

- In general there will be limited disruption of services. However, the replacement of water services (noted above) will require temporary shut-down of individual supply for a short period. When it is determined during construction that a temporary disruption is necessary to provide the necessary connections, the affected property owners will be notified.

### **Traffic Control**

- Due to the extent of work proposed, Princes Street will be closed to through traffic (i.e. open to local traffic only) and there may be times during construction that access to residential driveways is limited. Residents should be prepared to park off-site upon occasion and when necessary.
- Emergency Services will be made aware of the works proposed and the Contractor and Municipality will notify them when specific locations are under construction.

### **Covid-19**

- Due to potential concerns related to Covid-19, members of the public are asked to respect social distancing guidelines when in the vicinity of the work site.

If you have any questions or concerns about this project, please do not hesitate to contact Public Works.

Yours truly,

Adam Weishar, C.E.T.  
Director of Public Works